

Recent progress on the high-current testing facility for superconducting cables at CERN

A. Ballarino, CERN

Advisory Committee Meeting

IASS – Potsdam

29th November 2012

Outline

- Introduction
- MgB₂ electrical transfer lines: CERN activity in 2012
 - Superconducting links for the LHC machine
 - Conductor development and characterization
 - Development of cables for electrical transmission
 - Design of novel test station
- Plan for future activities
- Conclusions

Introduction

➤ Superconductivity at CERN → high-field magnets

➤ LHC: Nb-Ti @ 1.9 K

Very high and uniform current density

Small superconducting filament size


Precise dimensions

Appropriate and controlled Cu/non Cu ratio

In LHC: more than 240 000 km of Nb-Ti strand

➤ LHC upgrades: Nb₃Sn @ 1.9 K

LHC Strands



Nb-Ti (LHC Machine)

$J_c(4.2$ K, 6 T) \sim 2300 A/mm^2

$J_c(1.9$ K, 9 T) \sim 2300 A/mm^2



Nb₃Sn (LHC Upgrades)

$J_c(4.2$ K, 12 T) \sim 2500 A/mm^2

Cables for LHC Dipole Magnets


Performance specification

STRAND	Type 01	Type
Diameter (mm)	1.065	0.82
Cu/NbTi ratio	1.6-1.7 ± 0.03	1.9-2.0 ±
Filament diameter (µm)	7	6
Number of filaments	8800	642:
Jc (A/mm ²) @1.9 K	1530 @ 10 T	2100 @
µ ₀ M (mT) @1.9 K, 0.5 T	30 ±4.5	23 ±4
CABLE	Type 01	Type
Number of strands	28	36
Width (mm)	15.1	15.1
Mid-thickness (mm)	1.900 ±0.006	1.480 ±(
Keystone angle (degrees)	1.25 ±0.05	0.90 ±(
Cable Ic (A) @ 1.9 K	13750 @ 10T	12960 @
Interstrand resistance (µΩ)	10-50	20-8



Cable compaction ~ 91 %






$J_c(\text{MgB}_2, 4.2 \text{ K, s.f.}) \sim 10000 \text{ A/mm}^2$

Outline

- Introduction
- MgB₂ electrical transfer lines: CERN activity in 2012
 - Superconducting links for the LHC machine
 - Conductor development and characterization
 - Development of cables for electrical transmission
 - Design of novel test station
- Plan for future activities
- Conclusions

Powering of LHC Machine




- To limit the stored energy within one electrical circuit, the LHC is powered by sectors
- The main dipole circuits are split into 8 sectors to bring down the stored energy to ~ 1 GJ/sector
- Each sector (~ 2.9 km) includes 154 dipole magnets (powered in series) and ~ 50 quadrupoles


Powering Sector



~ 3.4 MA, > 3000 Current Leads, ~ 1500 Electrical Circuits

LHC Tunnel



In tunnel alcoves






27 × 6000 A
 48 × cables 600 A
 $I_{\text{tot}} = 190 \text{ kA}$

Multi-cable assemblies
 He gas cooling

Outline

- Introduction
- MgB₂ electrical transfer lines: CERN activity in 2012
 - Superconducting links for the LHC machine
 - Conductor development and characterization
 - Development of cables for electrical transmission
 - Design of novel test station
- Plan for future activities
- Conclusions


Columbus MgB₂ tape



4 × 0.67 mm²



Atot = 0.8 mm²
Asc = 0.0028 mm²
ff = 10 %



Φ ~ 1 mm

sem_2115 AL D8.9 x120 500 um


MFT281 T1

Columbus MgB₂ wire


Target performance characteristics

$I_c(20\text{ K}, 0.5\text{ T})$	> 500 A	A
$I_c(25\text{ K}, 0.5\text{ T})$	> 400 A	A
$I_c(30\text{ K}, 0.06\text{ T})$	> 300 A	A
$J_{c,eng}(20\text{ K}, 0.5\text{ T})$	> 630	A/mm ²
$J_{c,eng}(25\text{ K}, 0.5\text{ T})$	> 500	A/mm ²
$J_{c,eng}(30\text{ K}, 0.06\text{ T})$	> 380	A/mm ²
n-value (25 K, 0.5 T)	> 30	
Φ_{ext} of strand	< 1	mm
Number of filaments*	37/61/91	
Φ_{ext} of MgB ₂ filaments	< 50	μm
Copper stabilizer	≥ 12	%
RRR Copper stabilizer*	> 80	
Twist pitch of filaments*	≤ 100	mm
Bending radius*	< 100	mm
Critical tensile strain (RT)*	> 0.3	%
Unit length	1000	m

*Reacted wires



Measurements @ CERN (4.2 K) and Columbus (16 K and 20 K)



➤ Introduction

➤ Activity performed at CERN in 2012




- Conductor development and characterization
- Development of cables for electrical transmission
- Design of novel test station

➤ Plan for future activities



➤ Conclusions

1-kA Range Cables

$I_c(4.2 \text{ K, s.f.}) = 2070 \text{ A}$



10-kA Range Cables



1 cable \rightarrow 12 MgB₂ wires

$I_c(4.2 \text{ K, s.f.}) \sim 7300 \text{ A}$

$I_c(16 \text{ K, s.f.}) \sim 5100 \text{ A}$

6 cables

$I_c(16 \text{ K, s.f.}) \sim 21000 \text{ A}$

- Introduction

- Activity performed at CERN in 2012
 - Conductor development and characterization
 - Cables for electrical transmission
 - Design of novel test station

- Plan for future activities

- Conclusions

Conductor Characterization in Existing Test Stations




Test stations (4)

Ic measurement of wires

4.2 K or 1.9 K, 4 kA, 15 T

LSC ~20 cm (straight samples)



Fresca test station

Ic measurement of wires or cables

4.2 K or 1.9 K, 32 kA, 10 T

LSC up to 2 m

Development of a novel test station

Design a **new test station** for the electrical characterization of superconducting cables operated in **helium gas** at various temperatures in the range **5 K to 70 K**

Use of existing cryogenic and electrical infrastructure available in the laboratory SM-18:


20 kA DC power converter;

liquid He (**6 kW He refrigerator**);


as well as the space required for integration of long transfer lines

Test of cables with a length of up to **20 m**

Location of SM-18



CERN, SM-18 Laboratory




Refrigerator: 6 kW @ 4.5 K
(18 kW for test of LHC magnets)
25 000 LHe Dewar


Prévessin, French CERN site

Conceptual design


RT




Conceptual design



Conceptual design




System design






20-m Long Nexans Transfer Line










System Commissioning

- The cryostat is completely assembled and under leak test
- Two 20 m long cables, each made from one YBCO tape twisted with two copper strips, are integrated in the line
- The first cool-down is planned to take place before Christmas:
 - commissioning of the cryogenic system;
 - measurements at currents of up to ~ 2 kA

Plan for future activities



Conclusions

- The recent progress made on wire development - at Columbus – and on the design of a novel test station will enable us to test high-current MgB₂ cables in significant lengths (up to 20 m) as from beginning of 2013
- Several geometries of cables have been studied and will be tested
- Measurements will be performed in different operating conditions to fully assess the potential of MgB₂ for application to high-current long distance electrical transmission